

Rock Cut Road Transfer Station Optimization Project, Phase 2
5808 Rock Cut Road, Jamesville NY 13078
Onondaga County Resource Recovery Agency

Addendum to Contract Documents

September 7, 2022

This Addendum includes additional information to the Contract Documents dated August 3, 2022.

Contractors submitting proposals for the above-named project shall take note of the information included in this addendum regarding any changes, additions, deletions, clarifications, etc., in the Contract Documents, which shall become a part of and have precedence over anything contrarily shown or described in the Contract Documents, and as such shall be taken into consideration and be included in the Contractor's Bid Proposal.

This Addendum must be acknowledged in the Contractor's Bid Proposal.

Item No. 1:

Question: *Please confirm the overhead coiling door specifications.*

Based on the industrial and rigorous nature of the transfer station operations that take place in the vicinity of the proposed Rolling Service Door (*depicted on Sheet A-8 and covered within Technical Specifications Section 08 33 23 Overhead Coiling Doors*), the Rolling Service Door is intended to be specified as the Wayne Dalton Model 800F (*or approved substitution*) with a minimum wind load rating of 115 psf. The high wind loading rate was specified to attain the increased impact rating (*100 mph*) and 12-gauge galvanized steel flat-faced slats of the referenced tornado resistant Wayne Dalton Model 800F.

Item No. 2:

Question: *Will OCRRA be using an existing term contract to hire 3rd party hazardous materials abatement monitoring services, or will a RFP will be issued?*

Response:

A survey has already been completed, and no hazardous materials were identified, therefore no monitoring is anticipated at this time.